BEAM DECK: 1¾ SQ BEAMS. 2-5oz DYNEL/EPOXY; ½" OKUME; 6oz WEAVE/EPOXY.
BEAMLESS DECK. 2-5oz DYNEL/EPOXY; 9mm OKUME, 1.5oz MAT/EPOXY; ¾" NIDACOR, 1.5oz MAT/EPOXY; 6mm OKUME; 6oz WEAVE/EPOXY.

CUTOUTS DOUBLE AS ENGINE COMP. EXH VENTS

3/4 PLY

FLUSH

FLUSH

FLUSH

CUPBOARD
STBD
BINS PORT

FX

DUBDOCK PARTITIONS

BLOWER

VERTICLE LOCKER DIVIDER THIS SIDE ONLY. OTHER SIDE IS A SCOPPER LIP AND HATCH LAND. ACCESS BOW HDWR THROUGH CUTOUT IN ANCHOR LOCKER

SAILS

3/4 PLY BLOCK

3/4 PLY KING PLANK OVER DECK

1/2" DECK

½ PLEXI OR ON ½ PLY FRAME

3/8 MAHOG + ½ PLY FRAME

½ PLY

2x4

P&S

ANCHORS

FUELS LOCKER
VENTS TO
CUTOUTS

½ PLY

MAST, 26'6" POLE
LOWER 8' CUT FROM 6x6.
TRAPAZOID AT PARTNERS.
TRANSITIONS TO 5¼"
ROUND, JOIN TO HOLLOW
UPPER SECTION WITH
CLOTHSPIN SCARF,
12:1. 3" AT TIP

HEADSTAY ATTACHES 5' BELOW MAST TIP. CUBB JIB.
BALLANCE JIB FOR LIGHT AIR.
WISHBONE BOOM ATTCH 8' FROM STEP.

BALLANCE JIB

EXH TO PORT

½

SCALE:	APPROVED BY:	DRAWN BY
DATE:		REVISED
		DRAWING NUMBER