Structural Composites Inc.

Raw Data Summary

CLIENT:	Compmillenia
TESTS PERFORMED:	Compressive Strength/Modulus (ISO 14126)
TEST PROGRAM NAME:	7015-181
DATE TESTS PERFORMED:	12/21/2007

TEST RESULTS:

Specifications: E-LT3200 w/ Prime 20LV Vacuum Infused Panel

Conditions:

Sample Name	Sample ID	Width (in)	Depth (in)	Compressive Strength (psi)	Compressive Modulus (psi)	Maximum Load (lbs)
181-D	C1	0.6085	0.1375	29,486	2.689E+06	2,467
181-D	C2	0.5785	0.1250	33,169	3.503E+06	2,399
181-D	C3	0.5860	0.1265	35,335	2.269E+06	2,619
181-D	C4	0.6055	0.1195	39,166	6.430E+06	2,834
181-D	C5	0.5855	0.1200	25,621	2.793E+06	1,794
181-D	C6	0.6185	0.1210	33,391	8.599E+06	2,499
	Average		0.1249	32,695	4.381E+06	
	Std. Dev		0.0068	4,688	2.554E+06	

Loading Rate (in/min): 0.05

BK
Technician